
Panel Wiring Diagram Model DAX1 IR1 PT



Duplex Operation

High Level Alarm/Timer Override On: This float turns on th lag pump and activates the alarm light and audible alarm when lifted. The audible alarm may be silenced by pressing the illuminated PUSH TO SILENCE button on the front of the control panel. The pump will continue to run and the alarm light will remain on until the Pumps Off float is lowered

Timer On & Off: This float turns off the programmable timer when lowered. When this float is lifted the timer will be restarted. Note: The timer will start with its off cvcle.

Programmable Timer: The timer turns the lead pump on and off in a pre-set cycle. Note: The timer will start with its off cycle.

FACSIMILE:

Orenco Systems®

Incorporated

814 AIRWAY AVENUE

SUTHERLIN, OREGON

97479-9012


TELEPHONE:

(541) 459-4449

(541) 459-2884

Key - = Factory Wire = Field Wire

- = Alternate Field Wire = Audio Alarm, 115 VAC AL = Alarm Light AL = Alarm Light ALT = Duplex Alternator AS = Audio Silence Switch CCB = Controls Circuit Breaker CR1 = Override Relay = Intrinsically Safe Relay IR М = Motor Contactor PCB = Pump Circuit Breaker PT = Programmable Timer SR = Silence Control Relay TI = Terminal Link *Options СТ
- = Cycle Counter ETM = Elapsed Time Meter
- HT = Heater
- = Power Light PRL = Pump Run Light



neutral line.