



814 AIRWAY AVENUE SUTHERLIN, OREGON 97479-9012

TELEPHONE: (800) 348-9843 (541) 459-4449

WEBSITE:

www.orenco.com






Removal of the terminal link rail will separate the high level alarm and lag pump enable functions for timed dose operation or the high level alarm and lag pump on functions in demand dose

= Factory Wire = Field Wire = Alternate Field Wire = Audio Alarm, 115 VAC = Alarm Light

= Audio Silence Switch

Key



*Options

= Heater = Power Light = Pump Run Light = Test Switch

PL PRL TS

Remote Alarm Connections



Orenco Model AHW or equiv

Note: 115VAC signal is present during alarm conditions.

For MVP-DAX DM operation description, see drawing no. "EIN-CP-OP-2042".

> EDW-WD-DAX-142 Rev. 9.0 © 02/09/18